ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 10th April 1940.

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing Central College Old Boys' Association Building, Bangalore, published in pages 843-845, Part VI of the *Mysore Gazette*, dated 18th April 1940.

The last date of tender is 29th April 1940.

M. K. RAJAM IYENGAR,
Executive Engineer.

WATER SUPPLY DIVISION.

Abstract Notification.

The attention of the public is invited to page 853, Part VI of the *Mysore Gazette*, dated 18th April 1940, inviting tenders for the sale by the Department of 13 mild steel 20 feet span and 4 feet depth automatic sluice gates available at Chamarajsagar and Water Works, Thippagondanahalli.

The last date for receipt of sealed tenders is 13th May 1940.

The earnest money to be paid with the tender is Rs. 200 in cash.

M. K. NARASIMHA IYER,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification dated 11th April 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for repairing the revetment and sluice of Thattamachanahalli tank, Reg. No. 26 of Devanhalli Taluk, published on pages 848-850 of Part VI of the *Mysore Gazette*, dated 18th April 1940.

The last date for the receipt of the tender is 2 P.M. on 26th April 1940. Duplicate challan for having credited the deposit amount of Rs. 180 into the treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

Abstract Notification dated 12th April 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring Mandigere Minor tank, Reg. No. 85 of Nelamangala Taluk, published on pages 850-852 of Part VI of the *Mysore Gazette*, dated 18th April 1940.

The last date for the receipt of the tender is 2 P.M. on 4th May 1940. Duplicate challan for having credited the deposit amount of Rs. 170 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

KOLAR DIVISION.

Notification dated 17th April 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division up to 2 P.M. on 11th may 1940, for restoring Bussanahalli Hongekere Tank (unrestored minor) Reg. No. 318/692 of Kolar Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Bussanahalli Hongekere tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for earnest money of Rs. 180 paid to the treasury to the credit of "17(*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 11th May 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of March 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21 All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tender in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form.

Abstract estimate for restoring Bussanahalli Hongekere Tank (unrestored minor) Registered No. 318/692 of Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	I. Bund at R. L. 56·00.		Rs. a. p.		Rs. a. p.
1	Jungle clearing with roots complete	Grade	2 0 0	11	
2	Removing ant-hills and filling with sand ..	L. S.	..	..	
3	Earthwork excavation, cutting grip and trenches for the seat of new earth	Grade	2 0 0	14	
4	Earthwork to bund with lead, watering and consolidation, etc., complete	C.yd.	0 3 0	9,158	
5	Turfing the slopes of bund	S.yd.	0 0 9	4,661	
6	Removing and resetting old stone revetment with new jelly wedging	C.yd.	0 8 0	592	
7	New rough stone revetment with jelly backing ..	,,	1 8 0	470	
8	Providing and fixing new grade stones with figuring and painting	Each	1 8 0	14	
9	Do Index stones do ..	,,	0 6 0	14	
10	Do Register No. stone do ..	,,	3 0 0	1	
11	Removing and refixing B. M. stones with painting, etc.	,,	1 0 0	2	
	Total for Bund Rs.				
	II. Constructing a new pipe sluice with Cill at 43·00.				
1	Earthwork cutting open the bund	C.yd.	0 2 6	38	
2	Earthwork refilling with watering and consolidation	,,	0 2 6	42	
3	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	88	
4	Size stone in surki mortar	C.ft.	0 4 6	273	
5	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 6	78	
6	Cement pointing including raking joints (1 : 3) ..	Sqr.	3 8 0	3·80	
7	Providing 6″ diar. C. I. pipes with carting and fixing charges, etc., complete	R.ft.	3 0 0	36	
8	Providing a new plug and rod with locking arrangement, etc., complete	L. S.	..	..	
9	Rough stone work	,,	..	..	
	Total for sluice Rs. ..				

No.	Items of work.	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs. a. p.
	III. Constructing weir at Right at 51·00, 60 ft. long.				
1	Earthwork excavation	C.yd.	0 2 6	1⅓	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 0	36	
3	Size stone in surki mortar with through stones	,,	0 4 6	100	
4	Benching rock portion for required level	S.ft.	0 4 0	120	
5	Cement pointing and sundry items, etc.	L. S.	..	..	
	Total for waste weir Rs.				

Notification dated 18th April 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 11th May 1940, for restoring Thummalapalli Gyadari Kunte (unrestored minor) Reg. No. 337 of Srinivaspur Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Restoring Thummalapalli Gyadari Kunte." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 150, paid to the treasury to the credit of "17 (*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division, Kolar. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 11th May 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings, may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tender in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form.

Abstract estimate for restoring Thummalapalli Gyadari kunte, (unrestored minor) Registered No. 337 of Srinivaspur Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	I. Bund.		Rs. a. p.		Rs. a. p.
1	Jungle clearing with removal of with roots including removing ant-hills and filling them with sand and gravel	Grade	1 8 0	17	

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs. a. p.
2	Cutting grips and trenches for the seat of new earth	Grade	1 8 0	17	
3	Earthwork to bund from barrow pits including watering and tamping and lead charges	C.yd.	0 3 0	4,670	
3	(*a*) Removal of silt in the breach	,,	0 2 0	185	
	(*b*) Earthwork excavation in breach	,,	0 2 6	565	
	(*c*) Consolidating available earth in item 3 (*b*) above with watering, tamping and lead (using earth for bund)	C.yd.	0 1 0	565	
4	Turfing the slopes	S.yd.	0 0 9	3,875	
5	Providing and fixing new grade stones with bed slabs including carving figure and painting, complete	No.	1 8 0	17	
6	Providing and fixing Index stones do	,,	0 6 0	17	
7	Do B. M. stones fixed in concrete bed	,,	2 8 0	2	
8	Do Reg. No. and date stone	,,	3 0 0	1	
9	Removing and resetting old stone revetment with new jelly packing	C.yd.	0 6 0	224	
10	Rough stone work new up to R. L. 51·00 with jelly packing	,,	1 6 0	712	
11	Do pitching above R. L. 51·00 up to 54·00 R.L.	S.yd.	0 6 0	851	
	Total for Bund Rs.				
	II. Repairing Sluice No. I.				
	Repairs to front chamber	L. S.			
	III. Constructing a new rough stone weir at R. L. 51·00 *to a length of* 41 *ft. at left end.*				
1	Earthwork excavation in soft rocky soil	C.yd.	0 4 0	61	
2	Concrete stone jelly in surki mortar	C.ft.	0 4 0	32	
3	Size stone in surki mortar with through stones	,,	0 4 6	92	
4	Burnt stone slabs 6″ thick dressed and fixed in mortar bed	S.ft.	0 4 6	24	
5	Pointing with cement mortar after racking joints (1 : 3 proportion)	Sqr.	3 8 0	1·76	
6	Rough stone work new including lead and jelly wedging	C.yd.	1 6 0	25	
	Total for waste weir of 41 ft.—Rs.				
	IV. Repairing the existing rough stone weir at right end 68′ *long and extending the same to a further length of* 33′ *to make up* 101 *ft. long.*				
1	Earthwork exacavation in soft rock	C.yd.	0 4 0	22	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 0	36	
3	Size stone in surki mortar with bond stones	,,	0 4 6	112	
4	Burnt stone slabs 6″ thick dressed and fixed in mortar bed	S.ft.	0 4 6	27	
5	Pointing with cement mortar (1 : 3)	Sqr.	3 8 0	204	
6	Rough stone work new including lead and jelly wedging	C.yd.	1 6 0	31	
7	Removing and resetting old body wall with new jelly	,,	0 6 0	36	
8	Jelly wedging to old existing apron	S.yd.	0 1 0	151	
	Total—Rs.				

C. R. IYENGAR,
Executive Engineer.